Dominion Supplemental Projects

Transmission Expansion Advisory Committee July 9, 2024



Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



Need Number: DOM-2024-0018

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Thicket) to serve a data center in Henrico County with a total load in excess of 100 MW. The requested in-service date is 12/01/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 123 MW | Summer: 255 MW |
| Winter: 0 MW | Winter: 255 MW |





Dominion Transmission Zone: Supplemental

Customer Load Request

Need Number: DOM-2024-0019

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Gray Bark) to serve a data center in Henrico County with a total load in excess of 100 MW. The requested in-service date is 12/01/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 123 MW | Summer: 300 MW |
| Winter: 0 MW | Winter: 300 MW |





Need Number: DOM-2024-0020

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Saltwood) to serve a data center in Henrico County with a total load in excess of 100 MW. The requested inservice date is 12/01/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 150 MW | Summer: 300 MW |
| Winter: 0 MW | Winter: 300 MW |





Need Number: DOM-2024-0038

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Winterfield) to serve a data center in Charles City County with a total load in excess of 100 MW. The requested in-service date is 12/31/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 50 MW | Summer: 140 MW |
| Winter: 0 MW | Winter: 199 MW |





Need Number: DOM-2024-0039

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Summerfield) to serve a data center in Charles City County with a total load in excess of 100 MW. The requested in-service date is 12/31/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 50 MW | Summer: 164 MW |
| Winter: 104 MW | Winter: 277 MW |





Need Number: DOM-2024-0049

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service

Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Stockholm) to serve a data center in Henrico County with a total load in excess of 100 MW. The requested inservice date is 12/31/2026.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 150 MW | Summer: 300 MW |
| Winter: 0 MW | Winter: 300 MW |





Dominion Transmission Zone: Supplemental

Customer Load Request

Need Number: DOM-2024-0050

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service

Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request for a new substation (Letterkenny) to serve a data center in Henrico County with a total load in excess of 100 MW. The requested inservice date is 12/31/2026.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 75 MW | Summer: 300 MW |
| Winter: 0 MW | Winter: 300 MW |





Need Number: DOM-2024-0052

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

ODEC on behalf of Mecklenburg Electric Coop (MEC) has submitted a DP request for a new 230 kV delivery point (Nebula Sub) to serve a data center customer in Mecklenburg County with a total load in excess of 100 MW. Requested in-service date is 12/01/2028.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 0 MW | Summer: 12 MW |
| Winter: 12 MW | Winter: 26 MW |





Need Number: DOM-2024-0047

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service

Specific Assumption References:


Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

NOVEC has submitted a DP Request for a new substation (Pegasus) to serve a data center complex in Prince William County with a total load in excess of 100 MW.

Requested in-service date is 04/14/2027.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 22.8 MW | Summer: 87.0 MW |
| Winter: 22.8 MW | Winter: 87.0 MW |





Need Number: DOM-2024-0048

Process Stage: Need Meeting 07/09/2024

Project Driver: Customer Service

Specific Assumption References:


Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

DEV Distribution has submitted a DP Request to add a 3rd and 4th distribution transformer at Brickyard Substation in Manassas. The new transformers are being driven by significant area load growth.

Requested in-service date is 12/01/2026.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 49.0 MW | Summer: 164.4 MW |
| Winter: 49.0 MW | Winter: 147.6 MW |





Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: DOM-2023-0013

Process Stage: Solution Meeting 07/09/2024

Previously Presented: Need Meeting 03/07/2023

Project Driver: Customer Service

Specific Assumption References:


Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

NOVEC has submitted a DP Request for a new substation (Devlin) to serve a data center complex in Bristow with a total load in excess of 100 MW.

Requested in-service date is 05/01/2026.

| Initial In-Service Load | Projected 2029 Load |
|-------------------------|---------------------|
| Summer: 0.7 MW | Summer: 111.0 MW |
| Winter: 0.7 MW | Winter: 111.0 MW |





Dominion Transmission Zone: Supplemental Devlin 230kV Delivery – NOVEC

Need Number: DOM-2023-0013

Process Stage: Solutions Meeting 05/01/2026

Proposed Solution:

Interconnect the new substation by cutting and extending Line #2163 (Vint Hill – Dawkins Branch) to the proposed Devlin Substation. Terminate both ends into a GIS 230 kV four-breaker arrangement expandable to an ultimate of nine 230 kV GIS breakers in a breaker-and-a-half scheme.

Estimated Project Cost: \$42.0 M


Alternatives Considered:

No feasible alternatives

Projected In-service Date: 05/01/2026

Project Status: Engineering

Model: 2028 RTEP





Dominion Transmission Zone: Supplemental Operational Flexibility and Efficiency

Need Number: DOM-2024-0027

Process Stage: Need Meeting 04/30/2024

Project Driver: Operational Flexibility and Efficiency


Specific Assumption References:

Operational Flexibility and Efficiency will be evaluated per Dominion's Transmission Planning Criteria and Assumptions.

Problem Statement:

Planning studies and Dominion Energy Operations Engineering studies have identified overloads on 230 kV Line #2114 (Remington CT – Elk Run – Rollins Ford) based on a 2021 DNH analysis in the 2026 RTEP model (L/O Line 569 (Loudoun – Morrisville)).

The Dominion Energy Operations team needs a temporary solution to meet load growth expectations while avoiding thermal overloading on Line #2114 and accordingly provide flexibility for future construction outages.





Dominion Transmission Zone: Supplemental Operational Flexibility and Efficiency

Need Number: DOM-2024-0027

Process Stage: Solutions Meeting 07/09/2024

Proposed Solution:

Install an approximately 13.5 Ω series reactor at Remington CT on the terminal of Line #2114. (Dominion is repurposing an already in-stock/readily available reactor for this purpose and is only an interim measure until permanent transmission fixes are in place by 2029.)

Estimated Project Cost: \$4M


Alternatives Considered:

No feasible alternatives

Projected In-service Date: 6/01/2025

Project Status: Engineering

Model: 2026 RTEP





Need Number: DOM-2023-0052

Process Stage: Solution Meeting 07/09/2024

Previously Presented: Need Meeting 10/31/2023

Project Driver: Customer Service


Specific Assumption References:

Customer load request will be evaluated per Dominion's Facility Interconnection Requirements Document and Dominion's Transmission Planning Criteria.

Problem Statement:

ODEC on behalf of Mecklenburg Electric Coop (MEC) has submitted a DP request for a new 230 kV delivery point (Allen Creek Sub) to serve a data center customer in Mecklenburg County with a total load in excess of 100 MW. Requested in-service date is 12/01/2025 12/30/2025.

| Initial In-Service Load | Projected 2028 Load |
|-------------------------|---------------------|
| Summer: 0 MW | Summer: 80 MW |
| Winter: 12 MW | Winter: 110 MW |





Dominion Transmission Zone: Supplemental Butler Farm 230kV Delivery - DEV

Need Number: DOM-2023-0052

Process Stage: Solutions Meeting 07/09/2024

Proposed Solution:

• Construct Allen Creek 230 kV switching station with 4-breaker ring bus configuration. Customer will pay excess facility charges to install 6 more breakers.

 Cut Line #2258 (Finneywood – Cloud) and extend two 230kV lines to Allen Creek switching station.

Estimated Project Cost: \$30.0 M (Total)

Transmission Line \$8M 230kV Substation \$22M


Alternatives Considered:

No feasible alternatives, new station is adjacent to the existing transmission line.

Projected In-service Date: 12/30/2025

Project Status: Conceptual

Model: 2028 RTEP





Appendix



High level M-3 Meeting Schedule

| Assumptions | Activity | Timing |
|--------------------------|---|---|
| | Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| | Stakeholder comments | 10 days after Assumptions Meeting |
| | | |
| Needs | Activity | Timing |
| | TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| | Stakeholder comments | 10 days after Needs Meeting |
| | | |
| Solutions | Activity | Timing |
| | TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| | Stakeholder comments | 10 days after Solutions Meeting |
| | | |
| Submission of | Activity | Timing |
| Supplemental | Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| Projects & Local Plan | Post selected solution(s) | Following completion of DNH analysis |
| | Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| | Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |



Revision History

06/28/2024— V1 – Original version posted to pjm.com

